






**General Notes:**

- All Grading to Provide Positive Drainage to the Road.
- 0.5m Wide Asphalt Strips to be Removed and Reinstated Adjacent to Proposed Monolithic Sidewalk at Driveways.
- Asphalt Strips of Driveways to be Removed and Reinstated. Width Will Vary Depending on Drainage Requirements
- Protect Existing Trees Within Work Zone.

**Remarques Générales :**

- Tous les travaux de nivellement visent à permettre l'écoulement de l'eau.
- Bandes d'asphalte de 0,5 m de largeur à enlever et à rétablir à côté du trottoir monolithique proposé à la hauteur des entrées
- Bandes d'asphalte des entrées à enlever et à rétablir. La largeur variera selon les exigences liées au drainage.
- Les arbres se trouvant à l'intérieur du chantier seront protégés.

**Legend / Légende**

- |   |  |   |  |   |  |
|---|--|---|--|---|--|
|  | New 1.8m Monolithic Concrete Sidewalk /<br>Nouveau trottoir monolithique en béton de 1,8 m   |  | Sod /<br>Gazon                                     |  | Property line /<br>Limite de propriété |
|  | New 1.8m Concrete Sidewalk<br>(Including Existing Curb to Remain) /<br>Nouveau trottoir en béton de 1,8 m<br>(bordure existante à conserver) |  | New Asphalt Paving /<br>Nouveau pavage en asphalte |   |  |