



General Notes:

- All Grading to Provide Positive Drainage to the Road.
- 0.5m Wide Asphalt Strips to be Removed and Reinstated Adjacent to Proposed Monolithic Sidewalk at Driveways.
- Asphalt Strips of Driveways to be Removed and Reinstated. Width Will Vary Depending on Drainage Requirements
- Protect Existing Trees Within Work Zone.

Remarques Générales :

- Tous les travaux de nivellement visent à permettre l'écoulement de l'eau.
- Bandes d'asphalte de 0,5 m de largeur à enlever et à rétablir à côté du trottoir monolithique proposé à la hauteur des entrées
- Bandes d'asphalte des entrées à enlever et à rétablir. La largeur variera selon les exigences liées au drainage.
- Les arbres se trouvant à l'intérieur du chantier seront protégés.

Legend / Légende

- | | | | | | |
|--|---|--|---|--|-------------------------------------|
| | New 1.8m Monolithic Concrete Sidewalk / Nouveau trottoir monolithique en béton de 1,8 m | | Sod / Gazon | | Property line / Limite de propriété |
| | New 1.8m Concrete Sidewalk (Including Existing Curb to Remain) / Nouveau trottoir en béton de 1,8 m (bordure existante à conserver) | | New Asphalt Paving / Nouveau pavage en asphalte | | |