



#### Stage 2 LRT Confederation Line West Cleary Alignment Improvement

Public Information Session April 14, 2016







## Agenda

#### Background

- Functional Design & Alignment Improvements
- Confederation Line West Alignment Improvement
  - Overview
  - Benefits
  - Challenges Addressed
  - Construction Overview
  - Mitigation Measures
- Next Steps

Questions





## Background

- Functional designs were reviewed in more detail to assess feasibility and to evaluate opportunities to:
  - Minimize construction costs
  - Improve functionality
- Three (3) potential improved alignments have been identified
  - Confederation Line West Alignment
    - **1.** At Cleary and Richmond
  - Confederation Line East Alignment:
    - 2. East of Blair Station
    - 3. West of Montreal Road







Alignment Improvement at Cleary and Richmond:

Current functional design/EA alignment:

- Station entrance off Cleary limits visibility from Richmond Road
- Location of Cleary station limits connectivity to alternate modes of transportation
- Improved alignment:
  - Shifts Cleary Station along Richmond Road, improving connectivity and station visibility
  - Cost equivalent to the EA alignment





#### *Ottawa* Functional Design Cleary Alignment









## Improved Cleary Alignment









#### Improved Cleary Alignment Street Level Plan



# tawa Improved Cleary Alignment Potential Community Connectivity





## Improved Cleary Alignment Cleary Station Surface Elements

- LRT Station entrance to be complimented by:
  - Bus stops
  - Passenger pickup and drop off facility
  - Pedestrian connectivity
  - Bike lanes
  - Urban design treatments
  - Connection to NCC park/grade separated connections under Sir John A. Macdonald Parkway
  - NCC Linear Park
  - Opportunity created by purchase of 747 Richmond Road
  - Richmond Road Complete Streets initiative



**GC** Transpo





#### **Richmond Road Complete Street**

#### Public consultation planned for:

- Richmond Road Complete Street
- Richmond Road/Byron Linear Park/Byron Road all considered together
- Pedestrian connectivity
- Integration with surface station elements
- Preliminary surface station concept developed for discussion/integration with upcoming public consultation
- Concept is not an end but a beginning about what could be possible



**CC** Transpo





## Challenges Addressed

- Initial challenges that have been addressed
  - Utility conflicts watermain and combined storm and sanitary sewer
  - Insufficient straight track length in between curves to accommodate a station platform
  - Design challenges presented by a diagonal station platform below grade at Richmond Road







#### Functional Alignment Utility









#### Improved Alignment Utility





**GC** Transpo





## **Construction Overview**

- Cut and Cover technique for tunnel construction
- Access to all facilities maintained during construction
- Pre and Post construction condition surveys to be conducted
- Limits on noise and vibration during construction and operation
  - City Bylaw and contract requirements
  - Contractor innovation/incentives





## Construction Methodology Cut and Cover



1. Utility location and piling



2. Installation of decking



3. Excavation and soil removal





4. Construction of underground structure



5. Removal of decking/ street restoration

oc Transpo





### Common Mitigation Measures (Construction)

- Communicating scheduled and anticipated works
- Noise mitigation strategies
- Dust mitigation strategies
- Compliance with contract and City Bylaw for work hours
- Activities scheduled to create minimal impacts to traffic







#### Noise and Vibration Overview

- Wheel/rail noise/vibration a complex issue
- Benefits of Light Rail Train (LRT):
  - Lower weight than "heavy rail" subway cars
  - LRT vehicle is articulated
  - Resilient wheels
  - Equipped with wheel/rail lubrication system
  - Designed for much tighter curves than at Cleary
- Analysis shows that rail noise/vibration can be mitigated to acceptable levels given local conditions/mitigation measures
- Favourable conditions soft soil, no crossovers, reduced speeds, resilient wheels and continuous weld track







#### Stage 1 Alignment Comparison Noise and Vibration

- Very tight corridor to implement underground tunnel/stations
- Many buildings are 3-4m away from outside wall of tunnel
- Both sides of tunnel (residential, commercial, hotels, historic buildings)
- Mitigation measures range from:
  - None (direct fixation of track to tunnel floor)
  - Resilient fasteners
  - Floating slab
- Depends on context, age of building, sensitive receiver, etc.







#### Track Mitigation Options (Noise and Vibration)



#### Floating Slab (double tie isolated trackbed)









## Stage 1 – Mitigation Measures

Facility	Separation Between Tunnel/Development	Recommended Mitigation Measure
Christ Church	4 metres	Res <mark>ilient Fasteners</mark>
Marriott Hotel	4 metres	None
Place de Ville	4 metres	None
CBC	4 metres	Floating Slab
World Exchange Plaza	4 metres	None
NAC	35 metres	Floating Slab
Government Conference Centre (historic building)	12 metres	Floating Slab
Chambers Building (historic building)	Tunnel under corner of building	Floating Slab
50 Laurier Apartments	4 metres	Resilient Fasteners
	20 CC Tran	spo



#### Fan/Vent Shaft Noise

- Fans at each end of Cleary Station used for three purposes:
  - In an emergency (station/tunnel fire)
  - Testing (typically once/month)
  - To cool tunnel on hot summer days(if necessary)
- East ventilation shafts 20m away from 727 Richmond Road
- West end fans across the street from 75 Cleary Avenue
- Fans are slightly closer to buildings than in EA alignment
- Vent shaft noise not expected to be an issue given:
  - Modern construction of adjacent buildings
  - Fan silencers







# Improved Alignment Benefits

- Benefits of the improved alignment include:
  - Improved station accessibility
  - Improved visibility and community presence
  - Reduced property costs
  - Reduction in number of properties with development impacts







# Stakeholder Relations & Communications

- Extensive stakeholder engagement:
  - Dedicated local community liaison
  - Rapid response to all correspondence
  - Use of social media/website for notice of upcoming work
  - Communicate often/well on anticipated works
  - Stage 1 process has been well received
  - Applying "lessons learned" from Stage 1







## Next Steps

- 1. Public feedback on improved alignment
- 2. Opportunity for public input at FEDCO (May 3)
- 3. Consideration by City Council (May 11)
- Environmental Project Report(EPR) Notice of Study Commencement (June 2016)
- 5. Richmond Road Complete Street Town Hall Meeting (June 4)
- 6. EPR Notice of Study Completion (October)
- 7. Begin Property Acquisition (Q1 2017)
- 8. Scheduled construction start (2018)







# Questions?



oc Transpo

